


Delivering science and technology to protect our nation and promote world stability



Kilopower Reactor Using Stirling Technology (KRUSTY) Update



Rene Sanchez

26 March 2018

Outline

- Background
- Objectives of the KRUSTY experiment
 - KRUSTY test phases
- Comparison of measured data vs Simulations
 - Results of warm criticals
- Conclusions

Background

- 2012 NCERC and NASA conducted a small scale demonstration experiment called DUFF (Demonstration Using Flat-Top Fissions)
- 2014 Planning of the next demonstration experiment is examined
- 2015 Kilopower (KRUSTY) project gets started
- 2017 KRUSTY experiment begins (November)



Objectives

- The main objective of the KRUSTY experiment is to evaluate the operational performance of a compact reactor that closely resembles the flight unit NASA will use for deep exploration missions
- Test the dynamic behavior (transients) of the reactor
- Test the integrity of the fuel

KRUSTY test phases

Phase 1: Component Critical Measurements

- Critical configuration is determined
- BeO reflector worth measured
- B₄C control rod worth measurements
- Room temperature

Phase 3: Warm criticals

- 15 cent free run, 30 cent run, 60 cent run
- Moderate temperature rise (<450°C)


Phase 2: Cold Critical Measurements

- Heat pipes installed
- Stirling engines installed
- Above items in a vacuum chamber
- Critical configuration found
- B₄C control rod worth measurements
- Room temperature

Phase 4: High Temperature Operations


- Mission power profile is executed
- Significant temperature rise (800°C)

KRUSTY Experiment





Core for the KRUSTY Experiment



- Weight ~ 11 kg
- **Density** ~ 17.4 g/cc
- Uranium alloy (~7.5 wt% Mo)
- The uranium is isotopically enriched to ~ 93 wt% ²³⁵U


Phase 1: Component Criticals








Phase 2: Cold Criticals








Results(Component Criticals)

	BeO	Shim	B ₄ C	_	Source	Reactivity	Reactivity
	Height	BeO	Height	Source	Holder	Measured	Calculated
Sequential Operations Configuration	(in)	(in)	(in)	Holder	installed	(cents)	(cents)
Baseline initial critical	11.250	0	0	Al	х	9.50	10.6
Unload and reload 4" of BeO	11.250	0	0	Al	x	6.90	10.6
No change	11.250	0	0	Al	x	6.90	10.6
Only top source plug removed	11.250	0	0	Al	x	6.80	10.6
Only bottom source plug removed	11.250	0	0	Al	x	7.00	10.6
Both source plugs removed	11.250	0	0	Al	x	6.90	10.6
Plug replaced (baseline)	11.250	0	0	Al	x	8.50	10.6
Add 1/8" BeO	11.375	0	0	Al	x	51.60	52.4
No change	11.375	0	0	Al	х	50.00	52.4
Remove 1/8" BeO (baseline)	11.250	0	0	Al	х	9.20	10.6
Remove source and holder	11.250	0	0			2.30	1.6
No Change	11.250	0	0			2.30	1.6
Add 1/8" BeO	11.375	0	0			45.20	43.4
Add Al source holder	11.375	0	0	Al		46.80	46.2
No change	11.375	0	0	Al		48.20	46.2
Remove 1/8" BeO	11.250	0	0	Al	x	5.01	4.4

Los Alamos National Laboratory

Control rod worth measurement (Phase 2: cold criticals)






LA-UR-18-22334


Phase 3: Warm Criticals

March 7, 2018 (15 Cent Free run)




Maximum Temperature 218 °C

Warm Criticals




Warm Critical (30 cent) Zoom




6.6e-6 = 2.983 kw

5.5e-6 = 2.5 kw


Warm Critical (60 cents)




(60 cents Zoom)




28-hr Run 1st Shift



28 hr Run Last shift





Conclusions


- A lot of progress was made in the past year to accomplish the goals for this experiment
- Experimental and computational results compared quite well
- · Planning for the next series of experiments started

Future

Next mission

Thank you

This work was supported by the DOE Nuclear Criticality Safety program, funded and managed by the National Nuclear Security Administration for the Department of Energy.







Management Services Technical Solutions (MSTS)

